

NANDO'S GLOUCESTER ROAD

Type of work: **Refurbishment & Alterations**

Contract Type: **JCT Intermediate Contract with Contractors Design 2011**

Complete strip out and extend mezzanine floor, construct new first floor servery, wash up room & condiment area. Full refurbishment with new wall and ceiling finishes.

The clients designer had purchased some heavy stone column pieces and wanted them fitted over the main counter. A structural steel framework was constructed to hold the additional weight of the stone and we bolt fixed the stone pieces into position filling in the wholes so the fixings are hidden.

